


18"

6"

#4 REBAR @ 12" O/C



NOTES:

- HS-20 LOADING
- CONCRETE 5,000 PSI @ 28 DAYS
- REINFORCING: AS SPECIFIED, GRADE 60 REBAR
- MANUFACTURED IN ACCORDANCE WITH ASTM C-890
- 12" x 12" KNOCKOUT PROVIDED AS SHOWN
- WEIGHT: 4,500 LBS.

PEERLESS CONCRETE PRODUCTS CO.

SINCE 1959

sales@peerlessconcrete.com

246 Main Street
Butler, NJ 07405
973.838.3060p

www.peerlessconcrete.com

TRENCH DRAIN 12" X 12" X 120"
W/ CAST-IN GRATE & RAIL

CUSTOMER:

PROJECT:

SCALE: N.T.S.

DATE: 2/2026

EST#:

F-5